

Town of Butternuts
P.O. Box 318
Gilbertsville, NY 13776
607 783 2127

Air Line Spec Sheet:

The compressor will be mounted on the elevated storage area near the stairs.

The line shall consist of $\frac{3}{4}$ inch galvanized steel pipe.

The line shall be mounted as close to the ceiling as practical and inside the building. (8") All lines shall be secure to the walls.

All drops shall consist of $\frac{3}{4}$ " galvanized steel pipe and reach to within 5 feet of the floor. Each drop will have a $\frac{3}{4}$ " ball valve 1 foot from the bottom end followed by a 4" nipple, a cross with a $\frac{1}{4}$ " IM air chuck on one side and a $\frac{3}{8}$ Automotive air chuck on the other side. The center of the cross shall have a $\frac{3}{4}$ "x 4" nipple followed by $\frac{1}{2}$ " ball valve for a water drain.

4 drops to a distance of 5 feet above the floor will be spaced about every 20' along the Dry Brook side of the building wall.

A line across the building shall be mounted on the elevated storage support beam and contain 2 drops attached to two of the support posts.

A line shall run down the office side of the structure and have 3 drops located, one on the wall just past the office space. One about half way to the overhead doors, and one on the wall between the small overhead door and the first big overhead door.

Installation must be complete by October 20 2020.